



Seattle Archdiocese Office for Catholic Schools Design for Classroom WiFi Network Modernization Guidelines for IT Physical Infrastructure Design and Specifications


This document provides guidelines to school technology support staff responsible for developing and supervising the design and installation of new classroom computer/network cabling systems.

Contents:

- A. Standard floor rack network equipment rack and cabling/power components
- B. Wall mount rack with equipment profile
- C. Permanent Link Diagram of the cabling physical path to the classroom access point
- D. Specification and Standards: IEEE and BCSI
- E. Copper Cert Report: Example of the post-installation cabling certification report
- F. Wall Mount AP: Plan to attach wireless access point to a wall

Engineer: T. E. O'Callahan OCS Technology Strategy and Planning March 17, 2018 rev 8/19/19
Classroom WiFi Network Infrastructure Plan

Typical 19 Inch Floor Mount Rack Profile



Example: CHATSWORTH - 57003-703

REVISION DESCRIPTION		Typical Floor Mount Rack Example		
REV		SITE: Typical Rack	BLDG:	Location:
1		Engineer: Tom O'Callahan	DATE: 3/20/17	Project NAME:
2		ORIG: T. O'CALLAHAN	DATE: 3/17/15	SHEET: 1 of 1
3				




Not to SCALE SHEET SIZE: 11x8.5

Wall Mount Rack Examples and Equipment Profiles

Option 1: MDF/central network location
Hoffman Wall Mount Rack 12 RU
Part #: E19FMW12u20



Hoffman Wall Mount Rack
Equipment Position and
Cable Management Example



48 Cat 6 patch cables:
24 to left (red)
24 to right (green)
patch cables organized with velcro
into 6 cable bundles


Vertical cable management on right and left sides
Allen Tel Products AT55MR-S1
Vertical Cable Management D-Ring, 1 Rack Unit Wide

Allen Tel Products AT55WMP-1
1 Rack Unit mounted directly below
switch

TrippLite PDU RS1215-RA
12 Outlets (6F/6B) 1 Rack Unit 15 ft cord
1800 Watts

REV	REVISION DESCRIPTION	Not to SCALE SHEET SIZE: 11x8.5			
1	August 19, 2019: Add cable management detail		Hoffman Wall Mount Rack 12 RU	BLDG:	Location:
2			Engineer: Tom O'Callahan	DATE: 3/17/18	Project NAME:
3			ORIG: T. O'CALLAHAN	DATE: 3/17/15	SHEET: 1 of 1

End to End Classroom Cable Path



Permanent Link placed into a raceway/conduit to protect exposed cables

Figure 1: Drop ceiling WAP mounting






Figure 2: Beam ceiling WAP mounting



REV	REVISION DESCRIPTION	 Not to SCALE SHEET SIZE: 11x8.5	Cabling Design for Classroom Wireless Access Points		
			General Template	BLDG: All	Location:
			Engineer: Tom O'Callahan	DATE: 3/17/17	Project NAME:
			ORIG: T. O'CALLAHAN	DATE: 3/17/17	SHEET: 1 of 1

1. Bids shall provide detail on type of cabling. Include components necessary for full operation including installation. The attached diagram is guidance for a rack design. The components include: cabling, conduit, cable ways, race way, jacks, ground, busbar, patch panel, racks, cable management.
2. Dual 4 pair station wire will be terminated on an un-keyed 8 pin modular jack and shall conform to the appropriate performance specifications as set forth in EIA/TIA 568B or the equivalent.
3. All jacks shall be labeled with its appropriate assigned room number.
4. The number and location of jacks will be determined during a site visit. The estimated number is 25 jacks.
5. Installed equipment labels on installed items, such as access points and switches and other non-cable items, must include the Funding Request Number (FRN).
6. The wiring for wireless access points shall provide for mounting the access point in the middle of the classroom ceiling using the manufacturer specified mounting brackets.
7. The number of feet of cabling drops is an estimate only and the selected solution may differ from the estimation by a considerable amount.
8. Horizontal wiring shall be plenum rated.
9. Wires should run in a straight line at 90-degree angles to the building structure and be formed properly. Wire clamps/rings shall be placed 4’ horizontally or 8’ vertically. Cable/wire tie wraps or Velcro straps will be every 6’ horizontally or 8’ vertically. The installed cable must not be under tension greater than 25 pounds (11 kg). This will be visually apparent by the sag of the cables.
10. UTP cable shall be installed per the ANSI/TIA/EIA-569 EMI separation distances.
11. Cables shall not be laid directly on ceiling tiles, HVAC ducts or attach to sprinkler pipes, electrical conduit, ceiling tile hangers or any other structure not specifically intended for communications support.
12. The design/installation shall provide a minimum of 15ft (4m) service loop be provided in the horizontal permanent link to enable future patch panel or drop location move requirements.
13. Wiring/cabling and equipment must be properly installed and tested. Installer shall provide cabling test reports. Note: Cat 5e cabling must meet or exceed Cat 5e specifications at 100Mhz for near end/far end cross talk per IEEE 802.3 1000BASE-T (Gigabit Ethernet) standards. See Appendix A for an example.

14. The design/installation contractor must meet and comply with federal, state, and local codes and regulations including telecommunications industry standards: ANSI/BICSI, TIA, NEC/NFPA, IEEE. This is an example of such standards:
- ☑ ANSI/BICSI:
- ANSI/BICSI 002-2014 - Data Center Design & Implementation Best Practices
 - ANSI/BICSI 003-2014 - Building Information Modeling (BIM) Practices for Information Technology Systems
- BICSI:**
- Information Technology Systems Installation Methods Manual - 6th Edition
 - Outside Plant Design Reference Manual - 5th Edition
 - Telecommunications Distribution Methods Manual - 13th Edition
- TIA:**
- TIA-568-C.0 - Aug 14, 2012 - Generic Telecommunications Cabling for Customer Premises
 - TIA-568-C.1 - May 3, 2012 - Commercial Building Telecommunications Cabling Standard
 - TIA-568-C.2 - Nov 7, 2014 - Balanced Twisted-pair Telecommunications Cabling and Components Standards
 - TIA-568-C.3 - Oct 13, 2011 - Optical Fiber Cabling Components Standard
 - TIA-569 Rev B - Mar 12, 2015 - Telecommunications Pathways and Spaces
 - TIA-606 Rev B - Jun 22, 2012 - Administration Standard for Telecommunications Infrastructure
 - TIA-607 Rev B - Aug 21, 2013 - Generic Telecommunications Bonding and Grounding (Earthing) for Customer Premises
 - TIA-758 Rev B - Mar 27, 2012 - Customer-owned Outside Plant Telecommunications Infrastructure Standard
 - TIA-862 Rev A - Mar 30, 2011 - Building Automation Systems Cabling Standard
 - TIA-942 Rev A - Mar 2014 - Telecommunications Infrastructure Standard for Data Centers
 - TIA-1005 Rev A - Jan 7, 2015 - Telecommunications Standard for Industrial Premises
 - TSB-162 Rev A - Nov 1, 2013 - Telecommunications Cabling Guidelines for Wireless Access Points
- IEEE:**
- IEEE 802.3af-2003: Power over Ethernet (PoE).
 - IEEE 802.3at-2009: Power over Ethernet Plus (PoE Plus)
 - IEEE 802.11-2012: Wireless Networking
 - IEEE 802.3an-2006: 10GBASE-T 10 Gbps (1250 Mbps) Ethernet over Unshielded Twisted Pair (UTP)
 - IEEE 802.3bz: NBASE-T
- NFPA:**
- NFPA 70 - National Electrical Code - 2014 Edition
 - NFPA 70E - Standard for Electrical Safety in the Workplace - 2015 Edition


Post Installation:

Primary Contractor will email cabling test reports in a PDF format (Item 13) to tom.ocallahan@seattlearch.org within 20 days of completion.

REV	REVISION DESCRIPTION		Cabling Specifications and Standards		
			General Description	BLDG:	Location:
			Engineer: Tom O'Callahan	DATE: 3/17/17	Project NAME:
			ORIG: T. O'CALLAHAN	DATE: 3/17/17	SHEET: 1 of 1

Appendix A: Copper Certification Report Example

Copper Certification Report



Cable Label: P3 MDF D-01

Overall Result:

✓

Date & Time: 8/3/2016 2:27:28 PM

Building: Unspecified-Building

Limit Type: TIA - Cat 5e Permanent Link

Floor: Unspecified-Floor

Cable Name: CAT 5e UTP

Room: Unspecified-Room

Connector Name: UTP Mod Jack 5b

Rack: Unspecified-Rack

Site: Pope John Paul HS

Panel: Unspecified-Panel

Operator Name: Unspecified

Local Ser. No.: jt20311199

Remote Ser. No.: jt20311200

Local Adapter: Cat 6A Link

Remote Adapter: Cat 6A Link

Local Calibration Date: May 31 2016

Remote Calibration Date: May 31 2016

Device Software: 7.2

Reporting Software: Build_#424_7.2_2016 05 25_11 52 05

Wiremap: Pass

1

2

3

4

5

6

7

8

1

2

3

4

5

6

7

8

Wiremap: T568B

Length (m): 61.4

Value: Limit Margin

Cable NVP: 88.0

90.0 28.6

Propagation Delay (ns): 322.0

408.0 178.0

Delay Skew (ns): 10.0

44.0 34.0

Resistance (Ohms): 13.2

21.0 7.8

Insertion Loss: Pass

Worst Margin:

Worst Value:

Local:

Local:

Pair: 36

12

Value (dB): 1.9

14.2

Limit (dB): 3.1

20.9

Margin (dB): 1.2

6.7

Frequency (MHz): 2.50

99.00

dB

Local

-20

10

40

0

50

100 MHz

Return Loss: Pass

Worst Margin:

Worst Value:

Local:

Remote:

Local:

Remote:

Pair: 12

36

12

36

Value (dB): 29.1

19.2

26.8

19.2

Limit (dB): 17.2

12.3

13.9

12.3

Margin (dB): 11.9

6.9

12.9

6.9

Frequency (MHz): 29.95

93.75

64.50

93.75

dB

Local

-20

20

60

0

50

100 MHz

dB

Remote

-20

20

60

0

50

100 MHz

NEXT: Pass

Worst Margin:

Worst Value:

Local:

Remote:

Local:

Remote:

Pair: 36-45

36-45

36-45

36-45

Value (dB): 40.3

41.0

40.3

41.0

Limit (dB): 33.2

32.5

33.2

32.5

Margin (dB): 7.1

8.5

7.1

8.5

Frequency (MHz): 88.75

97.25

88.75

97.25

dB

Local

0

50

100

0

50

100 MHz

dB

Remote

0

50

100

0

50

100 MHz

ACR-F: Pass

Worst Margin:

Worst Value:

Local:

Remote:

Local:

Remote:

Pair: 36-12

45-36

45-36

36-45

Value (dB): 40.1

36.3

32.7

32.9

Limit (dB): 26.6

23.1

18.5

18.5

Margin (dB): 13.5

13.2

14.2

14.4

dB

Local

-20

40

100

0

50

100 MHz

dB

Remote

-20

40

100

0

50

100 MHz

Classroom WiFi Network Infrastructure Plan

Classroom WiFi Network Infrastructure Plan.vsd